

Exterior Bdys., T. 2 S., R. 32 E., W. M.

Chains		Feet
	N. on E. Bdy. of Sec. 36.	
	Var. 18°30' E.	
	Descend mountain.	
40.00	Set stone, 18 x 14 x 6 ins., for $\frac{1}{4}$ Sec. Cor.	
80.00	Set stone, 18 x 12 x 5 ins., for Cor. to Secs. 30, 31, 25 and 36.	60
	Land; hilly. Soil; 3rd rate. Timber; pine, fir & larch. Undergrowth; small pine.	
	Oct. 9, 1864.	
<hr/>		
	N. on E. Bdy. of Sec. 25	
	Var. 16°30' E.	
	Descend hill.	
30.00	Leave timber, brs. N.E. & S.W.	
40.00	Set stone, 18 x 10 x 6 ins., for $\frac{1}{4}$ Sec. Cor.	
80.00	Set stone, 16 x 12 x 10 ins., for Cor. to Secs. 24, 25, 19 & 30.	500
	Land; steep. Soil; 2nd rate. Good grass. Timber; scatter- ing pine.	
<hr/>		
	N. on E. Bdy. of Sec. 24.	
	Var. 20° 45' E.	
	Descend hill.	
40.00	Set stone, 18 x 6 x 6 ins., for $\frac{1}{4}$ Sec. Cor.	
80.00	Set stone, 24 x 12 x 10 ins., for Cor. to Secs. 18, 19, 13 and 24.	400
	Land; hilly. Soil; good 2nd rate.	
<hr/>		
	N. on E. Bdy. of Sec. 13,	
	Var. 16° 45' E.	
	Descend hill.	
40.00	Set stone, 16 x 12 x 6 ins., for $\frac{1}{4}$ Sec. Cor.	
80.00	Set post for Cor. to Secs. 12, 13, 7 & 18, in mound of earth, with charred stake, pits, trench, etc. as per instructions.	200
	Land; rolling. Soil; good 2nd rate.	