

Exterior Bdys., T. 2 S., R. 31 E., W. M.

Chains		Feet
	N. on E. Bdy. of Secs. 12.	
	Var. 20° E.	
	Descend hill.	
9.50	Foot of hill. E. fork of Birch Creek, 15 lks. wide, runs N.W.	50
19.70	Road brs. E. & W.	
	Samuel Smith's house brs. E., 6.00 chs. dist.	
25.00	Ascend hill.	
40.00	Set stone, 18 x 12 x 10 ins., for $\frac{1}{4}$ Sec. Cor.	
80.00	Set stone, 36 x 8 x 8 ins., for Cor. to Secs. 6, 7, 1 & 12.	1500
	Land; very steep. Soil; 2nd rate.	
<hr/>		
	N. on E. Bdy. of Sec. 1.	
	Var. 35°30' E.	
	Ascend hill.	
5.00	Top of hill brs. E. & W. Descend.	+ 100
40.00	Set stone, 16 x 8 x 6 ins., for $\frac{1}{4}$ Sec. Cor.	
46.70	Road brs. E. & W.	
80.00	Set post for Cor. to Tps. 1 & 2 S., Rs. 32 & 33 E., in mound of stone.	600
	Land; hilly. Soil; 2nd rate.	
<hr/>		
Extracts from Exterior Bdys. T. 3 S., R. 32 E., W. M. As surveyed by George S. Pershin, U.S. Deputy Surveyor, Under Contract No. 430, Dated March 23, 1882.		
<hr/>		
After having subdivided nearly all this Tp. and failed to find the Cors. on N. Bdy., I find the Cor. to Secs. 31 and 32, which is a stone about 18 x 12 x 7 on S. slope in mound of stone.		
I begin at this Cor. and retrace this N. Bdy.		
E. on the S. Bdy. of Sec. 32.		
	Var. 23°00' E.	
38.00	A ravine and spring branch, course S.W.	
40.00	Can find no trace of old Cor.	
	Set a basalt stone, 17 x 8 x 7 ins., 12 ins. in ground on N.W. slope for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on N. face, raised mound of stone alongside.	