

Exterior Bdys. T.3 S., R. 32 E., W.M.

Chains		Feet
	Set basalt stone, 12 x 10 x 8 ins., 8 ins. in ground, in creek bottom, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on N. face. A fir, 6 ins. diam., brs. N.17° W., 25 lks. dist. marked $\frac{1}{4}$ S., B.T. A fir, 12 ins. diam., brs. S.41° W., 41 lks. dist., marked $\frac{1}{4}$ S., B.T.	
41.75	Brook, 6 lks. wide, course N. Descent about 300 ft.	
49.00	Leave timber, course N. & S.	
61.00	Enter timber, course N. & S.	
80.00	Set basalt stone, 20 x 10 x 6 ins., 15 ins. in ground on N.E. slope, for Cor. to Secs. 34 & 35, marked with 4 notches on W. and 2 notches on E. edges. Ascent about 150 ft. A pine, 4 ins. diam., brs. N.64°E., 52 lks. dist., marked T.2 S., R.32 E., S.35, B.T. A pine, 4 ins. diam., brs. N.8°W., 70 lks. dist., marked T.2 S., R.32 E., S.34, B.T.	
	Land; surface very hilly. Soil; 3rd & 2nd rate. Timber; in places but mostly open, good grass.	
	<hr/>	
	E. on S. Bdy. of Sec. 35.	
		Var. 19° 30' E.
4.00	A spring branch, course N.	
21.50	Top of ridge, course N. & S. 300 ft. above last Cor. and spring branch.	
39.75	A spring branch, course N., about 200 ft. below top of ridge.	
40.00	Set basalt stone, 14 x 8 x 6 ins., 10 ins. in ground, on N.W. slope for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on N. face, from which, A tamarack, 10 ins. diam., brs. N.18°W., 5 lks. dist., marked $\frac{1}{4}$ S., B.T. A tamarack, 13 ins. diam., brs. S., 9 lks. dist., marked $\frac{1}{4}$ S., B.T.	

	May 27, 1882.	