

Subdivisional Lines, T. 2 S., R. 32 E., W. M.
As surveyed by Daniel Chaplin, U.S. Deputy Surveyor,
Under Contract No. 107,
Dated Sept. 21, 1864.

Chains		Feet
	<p>Note:</p> <p>The S. tier of sections in this Tp. is on a high, rocky mountains, unfit for settlement, cultivation or grazing and is therefore unsurveyed.</p> <p>I, therefore, commence at Cor. to Secs. 24 & 25 on E. Bdy. and run</p> <p>W. on true line bet. Secs. 24 & 25. Ascend hill.</p>	
40.00	Set stone, 18 x 14 x 4 for $\frac{1}{4}$ Sec. Cor. Top of hill brs. N. & S. Descend.	+300
80.00	Set stone, 20 x 8 x 6, for Cor. to Secs. 23, 24, 25 & 26. Land; steep and stony. Soil; 3rd rate.	-250
<hr/>		
	<p>N. bet. Secs. 23 & 24.</p> <p style="text-align: center;">Var. 19°30' E.</p> <p>Descend hill.</p>	
34.00	Foot of hill. Brook, 3 lks., course N.E.	
40.00	Set stone, 16 x 10 x 6, for $\frac{1}{4}$ Sec. Cor.	
80.00	Set stone, 18 x 16 x 5, for Cor. to Secs. 13, 14, 23 & 24 on E. slope of hill. Land; steep. Soil; 3rd rate. Good grass.	
<hr/>		
	E. on random line bet. Secs. 13 & 24.	
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor. Var	
79.84	Intersect E. Bdy., 64 lks. S. of Cor. to Secs. 13 & 24, from which, I run	
	S. 89°33' W. on true line bet. Secs. 13 & 24. Descend hill.	
31.37	Foot of hill. Brook, 4 lks. wide, runs N. Ascend hill.	-600
39.92	Set stone, 15 x 10 x 10, for $\frac{1}{4}$ Sec. Cor.	
79.84	Set Corner to Secs. 13, 14, 23 & 24. Land; hilly. Soil; 2nd rate.	+300
<hr/>		
	<p>N. bet. Secs. 13 & 14.</p> <p style="text-align: center;">Var. 19$\frac{1}{2}$° E.</p> <p>Descend hill.</p>	
40.00	Set stone, 17 x 10 x 5, for $\frac{1}{4}$ Sec. Cor.	
80.00	Set post for Cor. to Secs. 11, 12, 13 & 14, in mound of	