

Subdivisional Lines, T. 2 S., R. 32 E., W. M.

Chains		Feet
	E. on random line bet. Secs. 11 & 14.	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
80.42	Intersect N. & S. line, 32 lks. N. of Cor. to Secs. 11, 12, 13 & 14, from which, I run N.89°46' W. on true line bet. Secs. 11 & 14. Ascend hill along N. slope.	
40.21	Set stone, 12 x 6 x 8, for $\frac{1}{4}$ Sec. Cor.	
80.42	The Cor. to Secs. 10, 11, 14 & 15. Land; on N. hillside, sloping N. Soil; 2nd rate.	500
	N. bet. Secs. 10 & 11. Var. 21 $\frac{1}{2}$ ° E. Descend hill.	
24.00	Foot of hill.	500
26.00	Dry bed of Birch Creek, course N.W.	
30.20	Road brs. N.W. & S.E.	
40.00	Ascend steep rocky hill. Set stone, 15 x 8 x 7, for $\frac{1}{4}$ Sec. Cor.	
80.00	Set stone, 12 x 10 x 5, for Cor. to Secs. 2, 3, 10 & 11, on top of hill, brs. E. & W. Land; steep and stony. Soil; 3rd rate.	1000
	E. on random line bet. Secs. 2 & 11.	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
80.41	Intersect N. & S. line at Cor. to Secs. 1, 2, 11 & 12, from which, I run W. on true line bet. Secs. 2 & 11. Ascend hill.	
34.00	Top of hill brs. E. & W.	
40.20	Set stone, 18 x 9 x 6, for $\frac{1}{4}$ Sec. Cor.	
80.41	The Cor. to Secs. 2, 3, 10 & 11. Land; on high ridge brs. E. & W. Soil; 3rd rate.	
	N. on random line bet. Secs. 2 & 3. Var. 22 $\frac{1}{2}$ ° E.	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
80.60	Intersect N. Bdy., 21 lks. W. of Cor. to Secs. 2 & 3, from	