

Subdivisional Lines, T. 2 S., R.32 E., W.M.

Chains		Feet
	N. on random line bet. Secs. 3 & 4. Var. 19° E.	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
79.64	Intersect N. Bdy., 57 lks. W. of Cor. to Secs. 3 & 4, from which, I run S.0°24' W. on true line bet. Secs. 3 & 4. Descend hill.	
39.64	Set post for $\frac{1}{4}$ Sec. Cor., in mound of earth, with charred stake, pits, etc., as per instructions.	
57.30	Road brs. N.W. & S.E. Foot of hill.	
59.50	Birch Creek, 10 lks. wide, runs N.W. Ascend. hill.	500
79.64	The Cor. to Secs. 3, 4, 9 & 10. Land; hilly. Soil; 2nd rate. Nov. 25, 1864.	75
<hr/>		
	S. on true line bet. Secs. 27 & 28. Ascend hill.	
40.00	Set stone, 15 x 10 x 10, for $\frac{1}{4}$ Sec. Cor.	
80.00	Set stone, 17 x 9 x 8, for Cor. to Secs. 27, 28, 33 & 34. Land; hilly. Soil; 2nd rate. Good grazing.	500
<hr/>		
	W. on true line bet. Secs. 28 & 33. Descend hill. Var. 24° E.	
40.00	Set stone, 16 x 8 x 8, for $\frac{1}{4}$ Sec. Cor.	
80.00,	Set stone, 36 x 18 x 10, for Cor. to Secs. 28, 29, 32 & 33 Land; hilly. Soil; 2nd rate. On N. slope of mountain good grazing.	300
<hr/>		
	N. bet. Secs. 28 & 29. Descend hill. Var. 23° E.	
40.00	Set stone, 18 x 14 x 12, for $\frac{1}{4}$ Sec. Cor.	
80.00	Set stone, 20 x 15 x 10, for Cor. to Secs. 20, 21, 28 & 29. Land; hilly. Soil; 2nd rate.	700
<hr/>		
	E. on random line bet. Secs. 21 & 28.	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
80.50	Intersect N. & S. line at Cor. to Secs. 21, 22, 27 & 28, from which, I run	