

Subdivisional Lines, T. 2 S., R. 32 E., W.M.

Chains		Feet
	W. on true line bet. Secs. 21 & 28. Ascend hill.	
40.25	Set stone, 18 x 12 x 4, for $\frac{1}{4}$ Sec. Cor. Top of hill brs. N. & S. Descend.	+ 50
80.50	The Cor. to Secs. 20, 21, 28 & 29. Land; hilly. Soil; 2nd rate. Good grass.	-500
<hr/>		
	N. bet. Secs. 20 & 21. Descend hill. Var. 21° E.	
40.00	Set stone, 15 x 8 x 8, for $\frac{1}{4}$ Sec. Cor.	
45.50	Brook, 5 lks. wide, runs N.E.	
80.00	Set post for Cor. to Secs. 16, 17, 20 & 21, in mound of earth, with charred stake, pits, etc., as per instruct- ions. Land; hilly. Soil; 2nd rate.	
<hr/>		
	E. on random line bet. Secs. 16 & 21.	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
80.50	Intersect N. & S. line, 17 lks. S. of Cor. to Secs. 16 & 21, from which, I run S. 89° 53' W. on true line bet. Secs. 16 & 21. Ascend hill.	
38.00	Top of hill brs. N. & S. Descend.	+400
40.25	Set stone, 23 x 15 x 6, for $\frac{1}{4}$ Sec. Cor.	
59.00	Foot of hill. Brook, 5 lks. wide, runs N.E. Ascend.	-500
80.50	The Cor. to Secs. 16, 17, 20 & 21. Land; hilly. Soil; 2nd rate.	-300
<hr/>		
	N. bet. Secs. 16 & 17. Descend hill. Var. 21° E.	
40.00	Set stone, 20 x 10 x 5, for $\frac{1}{4}$ Sec. Cor.	
80.00	Set stone, 18 x 8 x 6, for Cor. to Secs. 8, 9, 16 & 17. Land; hilly. Soil; 2nd rate.	-600
<hr/>		
	E. on random line bet. Secs. 9 & 16.	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
80.37	Intersect N. & S. line, 21 lks. S. of Cor. to Secs. 15, 16, 21 & 22, from which, I run.	