

Subdivisional Lines, T. 2 S., R.32 E.,W.M.

Chains		Feet
	S.89°51' W. on true line bet. Secs. 9 & 16.	
40.19	Set stone, 16 x 8 x 8, for $\frac{1}{4}$ Sec. Cor.	
50.00	Ravine brs. N.	
80.39	The Cor. to Secs. 8, 9, 16 & 17.	
	Land; gently rolling. Soil; 2nd rate.	
<hr/>		
	N. bet. Secs. 8 & 9.	
	Descend hill. Var. 21 $\frac{1}{4}$ ° E.	
40.00	Set stone, 20 x 8 x 6, for $\frac{1}{4}$ Sec. Cor.	
69.00	Foot of hill. Ascend hill.	-500
80.00	Set post for Cor. to Secs. 4, 5, 8 & 9, in mound of stone.	
	Land; hilly. Soil; 3rd rate.	+150
<hr/>		
	E. on random line bet. Secs. 4 & 9.	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
79.89	Intersect N. & S. line, 27 lks. S. of Cor. to Secs. 3, 4, 9 & 10, from which, I run	
	S.89° 48' W. on true line bet. Secs. 4 & 9. Ascend hill.	
39.94	Set stone, 24 x 18 x 10, for $\frac{1}{4}$ Sec. Cor.	
53.00	Top of hill brs. N. & S. Descend.	+500
79.89	The Cor. to Secs. 4, 5, 8 & 9.	-400
	Land; hilly. Soil; 3rd rate.	
<hr/>		
	N. on random line bet. Secs. 4 & 5.	
	Var. 20 $\frac{1}{2}$ ° E.	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
80.70	Intersect N. Bdy., 15 lks. E. of Cor. to Secs. 4 & 5, from which, I run,	
	S.0°6' E. on true line bet. Secs. 4 & 5. Descend hill.	
40.70	Set stone, 16 x 12 x 6, for $\frac{1}{4}$ Sec. Cor.	
54.25	Ravine brs. W.	
80.70	The Cor. to Secs. 4, 5, 8, & 9.	
	Land; rolling. Soil; 3rd rate.	

Nov. 26, 1864.