

Subdivisional Lines, T. 2 S., R. 32 E., W.M.

Chains		Feet
	<p>A pine, 24 ins. diam., brs. N.17° W., 63 lks. dist., marked T.2 S., R.32 E., S.35, B.T.</p>	
	<p>No other trees found marked or blazed.</p>	
	<p>Thence I run</p>	
	<p>N. on true line bet. Secs. 35 & 36.</p>	
	<p>Var. 21° 00' E.</p>	
	<p>Ascend through timber.</p>	
22.50	<p>Summit of ridge, falls N.W. Descend 15°</p>	150
33.50	<p>Canyon, running water, 4 lks. wide, course N.65° W.</p>	700
40.00	<p>Set basalt stone, 16 x 8 x 4 ins., 12 ins. in ground, for ¼ Sec. Cor., marked ¼ on W. face, from which, A pine, 8 ins. diam., brs. E., 8 lks. dist., marked ¼ S., B.T. A pine, 30 ins. diam., brs. S.70° W., 24 lks. dist., marked ¼ S., B.T.</p>	
	<p>on W. face of hill.</p>	
40.50	<p>Leave timber.</p>	
68.00	<p>Summit of ridge, falls W. Descend 10°</p>	100
80.00	<p>The Cor. to Secs. 25, 26, 35 & 36.</p>	
	<p>Land; mountainous, 80.00 chs.</p>	
	<p>Soil; stony, 5th rate.</p>	
	<p>Timber; pine, fir & tamarack, 40.50 chs. open.</p>	
<hr/> <p>S. bet. Secs. 26 & 27.</p>		
	<p>Var. 20° 00' E.</p>	
12.50	<p>Ravine, running water, course W. Ascend 15°.</p>	
28.00	<p>Summit of ridge, falls N.W. Descend 20°</p>	200
40.00	<p>Set basalt stone, 20 x 12 x 10 ins., 15 ins. in ground, for ¼ Sec. Cor., marked ¼ on W. face, and raised mound of stone, 1½ ft. high x 3½ ft. base over Cor., on W. hill- side. Pits impracticable.</p>	
50.00	<p>Enter timber.</p>	
54.00	<p>Ogilvey Creek, 8 lks. wide, N.45° W. Ascend 25°.</p>	
80.00	<p>Set basalt stone, 12 x 12 x 8 ins., 8 ins. in ground, for Cor. to Secs. 26, 27, 34 & 35, marked 1 notch on S., and 2 notches on E. edge, and raised mound of stone,</p>	