

## Subdivisional Lines, T. 2 S., R. 32 E., W.M.

Chains		Feet
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
80.50	Intersect S. Bdy. of Twp., 6 lks. W. of Cor. to Secs. 4, 5, 32 & 33, which is a basalt stone, 18 x 14 x 4 ins., loose, in mound of stone, $1\frac{1}{2}$ ft. high x $3\frac{1}{2}$ ft. base., marked 4 notches on E. and 2 notches on W. edges. Thence I run N.0° 02 $\frac{1}{2}$ ' W. on true line bet. Secs. 32 & 33. Var. 22° 00' E.	
7.50	Enter timber.	
12.50	Gulch, course W. Ascend	-200
13.00	Leave timber.	
25.50	Summit of ridge, falls W. Descend 25°	+900
26.00	Wagon road brs. N.W. & S.E.	
40.50	Set basalt stone, 10 x 8 x 7 ins., 8 ins. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on W. face and raised mound of stone $1\frac{1}{2}$ ft. high x $3\frac{1}{2}$ ft. base over Cor. Pits impracticable, from which, A pine, 30 ins. diam. brs. N.80° W., marked $\frac{1}{4}$ S., B.T. A fir, 24 ins. diam., brs. E., 100 lks. dist., marked $\frac{1}{4}$ S., B.T.	
49.00	Pole and wire fence. Enter field.	
56.00	Leave field at S.E. Cor. of same.	
58.50	Cowshed. Sam'l Warner's house brs. E. 450 lks. dist.	
60.00	Foot of descent.	
60.60	Brook, 5 lks. wide, course N.W. Ascend.	
62.25	Wagon road brs. N.W. & S.E.	
75.00	Summit of ridge falls W. Descend 20°	+100
80.50	The Cor. to Secs. 28, 29, 32 & 33. Land; mountainous, 72.50 chs. Soil; 4th rate, stony. Timber; pine, fir and tamarack, 5.50 chs. Underbrush same, 2.00 chs. Good grass. Oct. 3, 1891.	
	W. bet. Secs. 29 & 32. Descend 20° Var. 20° 40' E.	