

Subdivisional Lines, T. 2 S., R. 32 E., W: M.

Chains		Feet
	N. on true line bet. Secs. 31 & 32. Var. 24°00' E.	
25.00	Summit of ridge falls W. Descend 20°	1000
40.00	Set basalt stone, 14 x 8 x 6 ins., 10 ins. in ground, for ¼ Sec. Cor., marked ¼ on W. face; dug pits, 18 x 18 x 12 ins. N. & S. of Cor., 5½ ft. dist., and raised mound of earth, 2 ft. high x 4½ ft. base over Cor., on E. Hillside.	
50.90	Pole fence, brs. E. & W.	
80.00	The Cor. to Secs. 29, 30, 31 & 32. Land; mountainous, 80.00 chs. Soil; 4th rate. Timber; none, nor brush. Good grass. Oct. 4, 1891.	
	W. on random line bet. Secs. 30 & 31. Var. 20° 05' E.	
40.00	Set temp. ¼ Sec. Cor.	
80.00	" " Cor. to Secs. 25, 30, 31 & 36. Finding no traces of any old Cor., I commence at S.W. Cor. to this Tp., which is a post, 4 x 4 ins., 24 ins. above ground, marked R.31, S.36 on N.W. face. No other visible marks, in mound of earth, 1½ ft. high x 4 ft. base on N. hillside, 200 lks. E. of ravine N.E. Thence I run N. on W. Bdy. of Sec. 31. Descend. Var. 18° 45' E.	
21.00	Stanley Creek canyon N.75° W. Ascend.	
40.00	Set temp. ¼ Sec. Cor.	
79.96	Intersect E. & W. line, 25 lks. E. of Cor. to Secs. 25, 30, 31 & 36, on W. Bdy. of Tp., which is a basalt stone, 18 x 15 x 10 ins., lying loose on ground on W. slope, marked 5 notches on 1 edge. I raised mound of stone, 2 ft. high x 4 ft. base over this stone, which I first set 12 ins. in ground, with the 5 notches on N. Thence I run	