

1.

N. Bdy., T.3 S., R.33 E., W.M.  
 As surveyed by Rufus S. Moore, U.S. Deputy Surveyor,  
 Under Contract No. 451,  
 Dated June 12, 1882.

Chains	Feet
	N. on E. Bdy. of Sec. 1.
	Var. 21° E.
80.00	Set post, 5 ft. long, 4 ins. sq., 24 ins. in ground, for Cor. to Tps. 2 & 3 S., R. 33 E., marked R.33 E. on W. T.2 S., S.36 on N., and T.3 S., S.1 on S. faces, with 6 notches on N. & S. & W. faces, from which, A tamarack, 6 ins. diam., brs. N.27° E., 42 lks. dist. marked T.2 S., R.34 E., B.T. A fir, 15 ins. diam., brs. N.23° W., 44 lks. dist., marked T.2 S., R.33 E., S.36, B.T. A fir, 9 ins. diam., brs. S.28° W., 25 lks. dist., marked T.3 S., R.33 E., S.1, B.T. A pine, 11 ins. diam., brs. S.45° E., 63 lks. dist., marked T.3 S., R.34 E., B.T. Land; high and mountainous. Soil; 2nd rate. Heavily timbered with pine, fir and tamarack. Dense pine and fir undergrowth. Nov. 6, 1882.
	From the Cor. to Tps. 2 & 3 S., R. 33 E., I run W. on N. Bdy. of Sec. 1 Var. 19° 30' E.
7.00	Descend hill, brs. N. & S.
19.25	Spring branch, 2 lks. wide, in ravine, course N. 300 ft. deep. Ascend.
40.00	Set post, 3 ft. long, 3 ins. sq., 24 ins. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ S. on N. face, from which, A pine, 8 ins. diam., brs. N.74° W., 53 lks. dist., marked $\frac{1}{4}$ S., B.T. A pine, 7 ins. diam., brs. S.39° W., 43 lks. dist., marked $\frac{1}{4}$ S., B.T. 300 ft. above ravine.