

Exterior & Subdivisional Lines, T.2 S., R.33 E., W.M.

| Chains | | Feet |
|--------|--|--------------------------|
| 40.00 | Set temp. $\frac{1}{4}$ Sec. Cor. | |
| 80.80 | Intersect N. & S. line, 25 lks. N. of Cor. to Secs. 13, 14, 23 & 24. Thence I run N. $89^{\circ} 49'$ W., on true line bet. Secs. 14 & 23. Var. $20^{\circ} 00'$ E. Descend. | |
| 2.31 | Canyon, course S.W. | Ascend. |
| 11.81 | Summit of ridge falls S.W. | Descend. |
| 18.06 | Canyon, course S.W. | Ascend, |
| 33.06 | Summit of mountain falls S. Descend steep stony mountain. | |
| 40.40 | Set basalt stone, 20 x 12 x 10 ins., 12 ins. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on N. face. Raised mound of stone, $2\frac{1}{2}$ ft. high x $3\frac{1}{2}$ ft. base over Cor., on hillside facing W. Pits impracticable. | |
| 58.56 | Canyon, course S. | Ascend. |
| 71.81 | Summit of mountain falls S. | Descend. |
| 80.80 | The Cor. to Secs. 14, 15, 22 & 23. Soil; stony 5th rate. Some grass. The whole line runs over mountainous land. | |
| | S. bet. Secs. 22 & 23. Descend. | Var. $17^{\circ} 30'$ E. |
| 29.65 | Canyon, course S.W. | Ascend, |
| 33.00 | Summit falls S.W. | Descend. |
| 38.50 | Wagon road brs. E. & W. | |
| 38.65 | Fence brs. E. & W. | |
| 40.00 | Set basalt stone, 14 x 12 x 10 ins., 10 ins. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on W. face; dug pits, 18 x 18 x 12 ins., N. & S. of stone, $5\frac{1}{2}$ ft. dist. Raised mound of earth, 2 ft. high x $3\frac{1}{2}$ ft. base over Cor., from which, A fir, 40 ins. diam., brs. S. 15° E., 39 lks. dist., marked $\frac{1}{4}$ S., B.T. A fir, 35 ins. diam., brs. S. 10° W., 25 lks. dist., marked $\frac{1}{4}$ S., B.T. | |
| | | Sept. 24, 1890. |