

Exterior & Subdivisional Lines, T.2 S., R.33 E., W.M.

Chains		Feet
	Scattering pines & firs on Birch Creek. The whole line runs over mountainous land.	
		Sept. 25, 1890.
	S. bet. Secs. 26 & 27.	
		Var. 20°30' E.
	Descend Mountain.	
17.50	Enter timber	
21.75	Canyon, course N.E. Ascend steep stony mountain.	
40.00	Set basalt stone, 18 x 10 x 6 ins., in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on W. face and raised mound of stone, 2 ft. high x $3\frac{1}{2}$ ft. base over Cor., pits being imprac., on N.W. hillside, from which, A fir, 60 ins. diam., brs., up hill, N.70° E., 93 lks. dist., marked $\frac{1}{4}$ S., B.T.	
	No other tree in limits.	
80.00	Set basalt stone, 18 x 10 x 4 ins., 12 ins. in ground, for Cor. to Secs. 26, 27, 34 & 35, marked 5 notches on N., 2 notches on E. faces. Raise mound of stone, $1\frac{1}{2}$ ft. high x $3\frac{1}{2}$ ft. base over Cor., on E. side of mountain, from which, A fir, 18 ins. diam., brs. N.82° E., 250 lks. dist., marked T.2 S., R.33 E., S.26, B.T. A pine, 30 ins. diam., brs. S.72° E., 240 lks. dist., marked T.2 S., R.33 E., S.35, B.T. A pine, 18 ins. diam., brs. N.72° W., 127 lks. dist., marked T.2 S., R.33 E., S.27, B.T.	
	No other tree within limits in Sec. 34.	
	Soil; stony 5th rate. Good grass.	
	Timber; pine, fir and tamarack, scattering along the whole line.	
	Land; mountainous, 80.00 chs.	
	E. on random line bet. Secs. 26 & 35.	
		Var. 13°00' E.
	Descend steep mountain.	