

Exterior & Subdivisional Lines, T.2 S., R.33 E., W.M.

| Chains | | Feet |
|--------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------|
| | <p>S.3 on S.W</p> <p>S.34 on N.W. faces, with</p> <p>1 notch on W. and</p> <p>2 notches on E. edges, from which,</p> <p>A pine, 6 ins. diam., brs. N.30° E., 32 lks. dist., marked T.2 S., R.33½ E., S.35, B.T.</p> <p>A fir, 40 ins. diam., brs. S.75° E., 11 lks. dist., marked T.3 S., R.33½ E., S.2, B.T.</p> <p>A tamarack, 30 ins. diam., brs. S.48° W., 6 lks. dist., marked T.3 S., R.33½ E., S.3, B.T.</p> <p>A fir, 4 ins. diam., brs. N.25° W., 21 lks. dist., marked T.2 S., R.33½ E., S.34, B.T.</p> <p>Thence I run</p> <p>N. on true line bet. Secs. 34 & 35.</p> <p style="text-align: right;">Var. 20°10' E.</p> <p>Through thick timber, on level land.</p> | |
| 25.50 | Leave thick timber, continue through scattering timber, on level land. | |
| 39.83 | <p>Set basalt stone, 17 x 10 x 4 ins., 12 ins. in ground, for</p> <p>¼ Sec. Cor., marked ¼ on W. face; dug pits, 18 x 18 x 12</p> <p>ins., N. & S. of stone, 5½ ft. dist. Raised mound of</p> <p>earth & stone, 2 ft. high, 3½ ft. base over Cor., from</p> <p>which,</p> <p>A pine, 24 ins. diam., brs. N.35° W., 62 lks. dist., marked ¼ S., B.T.</p> <p>A pine, 10 ins. diam., brs. N.82° E., 43 lks. dist., marked ¼ S., B.T.</p> | |
| 49.33 | Leave scattering timber, on level land. | |
| 58.33 | Descend mountain, stony surface. | |
| 62.33 | Enter timber. | |
| 79.83 | <p>The Cor. to Secs. 26, 27, 34 & 35.</p> <p>Land; mountainous.</p> <p>Soil; 4th rate. Good grass.</p> <p>Of this line, 25.50 chs., passes through a dense black</p> <p>pine thicket, with occasional fir and larch trees, and</p> <p>fallen trees in abundance. Of the remaining part of the</p> | |