

Extension & Subdivisional Lines, T.2 S., R.33 E., W.M.

Chains		Feet
	high x $4\frac{1}{2}$ ft. base over Cor.; pits impracticable.	
	Note:	
	This Cor. is set at $\frac{1}{2}$ the distance bet. Sec. Cor., and is 618 lks. W. of the Daly Wagon Road.	
46.50	The Cor. to Secs. 9, 10, 15 & 16.	
	Land; mountainous, 46.50 chs. No timber.	
	Soil; stony 4th rate. Good grass.	
	S. bet. Secs. 15 & 16.	
	Ascend. Var. $19^{\circ}45'$ E.	
10.00	Summit of ridge falls S.W. Descend, steep and stony.	
26.00	Canyon, course S. 38° W. Ascend 50°	-450
34.50	Summit falls S.W. Descent, steep & stony. 50°	+250
39.00	Canyon, 75' lower than summit at 34.50. Ascent, steep & stony. 50°	
40.00	Set basalt stone, 16 x 8 x 8 ins., 12 ins. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on W. face; dug pits, 18 x 18 x 12 ins., N. & S. of stone, $5\frac{1}{2}$ ft. dist. Raised mound of earth, 2 ft. high x $4\frac{1}{2}$ ft. base over Cor., on N. hillside.	
45.00	Summit of ridge falls S.W. Descend.	
64.50	Wagon road, course N.W. & S.E.	
64.58	Pole fence " " " "	
66.50	Birch Creek, 20 lks. wide, runs N.W.	
72.12	Cabin brs. W. 20 lks. dist.	
74.00	Pole fence brs. N.W. & S.E. Ascend steep mountain 43° .	
80.00	Set basalt stone, 14 x 8 x 6 ins., 10 ins. in ground, for Cor. to Secs. 15, 16, 21 & 22, marked 3 notches on S., 3 notches on E., and raised mound of stone, 2 ft. high x $4\frac{1}{2}$ ft. base over Cor., from which, A pine, 24 ins. diam., brs. N. $12^{\circ}30'$ E., 157 lks. dist., marked T.2 S., R.33 E., S.15, B.T.	
	No other tree in limits. Pits impracticable.	
	Land; mountainous, 80.00 chs.	
	Timber; scattering pine & fir.	
	Soil; stony 4th rate. Good grass.	