

## Exterior &amp; Subdivisional Lines, T.2 S., R.33 E., W.M.

Chains		Feet
	1½ ft. high x 4½ ft. base over Cor. on W. hillside. Pits impracticable.	
43.00	Leave timber.	
47.00	Summit of ridge falls W. Descend grassy slope	+500
65.00	Canyon N.85°W. Enter brush. Ascend abruptly 40°	-100
80.00	Set basalt stone, 14 x 8 x 6 ins., 10 ins. in ground, for Cor. to Secs. 21, 22, 27 & 28, marked 2 notches on S. face and 3 notches on E. face; dug pits, 18 x 18 x 12 ins. in each Sec. Cor., 5½ ft. dist. Raised mound of earth, 2 ft. high x 4½ ft. base over Cor. on E. slope of hill, from which,  A dead pine, 30 ins. diam., brs. N.5° W., 50 lks. dist., marked R.33 E., S.21, B.T.  A dead pine, 24 ins. diam., brs. N.40° E., 76 lks. dist., marked T.2 S., S.22, B.T.  Land; mountainous and stony, 75.35 chs.; level 4.65 chs. Timber; pine, fir and tamarack, undergrowth of same 19 chs. Soil; 4th rate. Good grass.  §§§	
	E. on random line bet. Secs. 22 & 27.  Var. 19°45' E.  Descend steep, stony mountain.	
40.00	Set temp. ¼ Sec. Cor.	
79.20	Intersect N. & S. line at Cor. to Secs. 22, 23, 26 & 27. Thence I run W. on true line bet. Secs. 22 & 27. Ascend. Var. 20°30' E.	
24.20	Summit of ridge falls N. Descend 48°	+300
34.20	Deep ravine, course N. Ascend.	-300
39.60	Set basalt stone, 12 x 8 x 6 ins., 8 ins. in ground, for ¼ Sec. Cor., marked ¼ on N. face; dug pits, 18 x 18 x 12 ins. E. & W. of stone, 5½ ft. dist. Raised mound of earth, 2 ft. high x 4½ ft. base over Cor., on N. hillside.	
46.50	Summit of ridge, N.W. & S.E. Descend.	
51.70	Wire fence " "	
60.95	Ravine, course N.W. Ascend.	