

## Exterior &amp; Subdivisional Lines, T.2 S., R.33 E., W.M.

Chains			Feet
66.70	Summit of ridge falls N.W.	Descend.	
73.95	Ravine, course N.	Ascend 40°	-100
79.20	The Cor. to Secs. 21, 22, 27 & 28. Land; mountainous & stony, 55 chs. Remainder, level. No timber. Soil; 4th rate. Good grass.		
<hr/>			
	S. bet. Secs. 27 & 28.	Var. 19°45' E.	
	Ascend steep, brushy mountain 30°		
6.50	A spring, in rock, brs. W. 25 lks. dist.		
18.50	Summit of ridge N.W. & S.E. Descend, steep & stony.		
27.00	Enter brush.		
28.00	Ravine, course N.W.	Ascend.	-200
40.00	Set basalt stone, 16 x 10 x 6 ins., 12 ins. in ground, for $\frac{1}{2}$ Sec. Cor., marked $\frac{1}{2}$ on W. face. Raised mound of stone 2 ft. high x 4 $\frac{1}{2}$ ft. base over stone, from which, A fir, 12 ins. diam., brs. E. 100 lks., marked $\frac{1}{2}$ S.B.T. No other tree in limits. Sept. 16, 1891.		
46.00	Summit of ridge brs. N. & S.		
80.00	Set basalt stone, 12 x 8 x 6 ins., 8 ins. in ground, for Cor. to Secs. 27, 28, 33 & 34, marked 1 notch on S. & 3 notches on E. faces. Pits impracticable. Raised mound of stone, 1 $\frac{1}{2}$ ft. high x 4 $\frac{1}{2}$ ft. base over Cor. Land; mountainous & stony, 46 chs. Comparatively level, 34 chs. A few scattering pines & firs. Soil; 4th rate. Good grass.		
<hr/>			
	E. on random line bet. Secs. 27 & 34.	Var. 20°10' E.	
	Descend abruptly 50°		
40.00	Set temp. $\frac{1}{2}$ Sec. Cor.		
80.00	Intersect N. & S. line, 60 lks. S. of Cor. to Secs. 26, 27, 34 & 35. Thence I run Var. 13°00' E.		
	S. 89°34' W. on true line bet. Secs. 27 & 34.		