

Exterior & Subdivisional Lines, T.2 S., R.33 E., W.M.

Chains	Feet
	T.3 S., R.33 E., S.1 on S.E.
	T.3 S., R.33 E., S. 2 on S.W. angles
	T.2 S., R.33 E., S.35 on N.W. faces,
	from which,
	A pine, 20 ins. diam., brs. N.40° E., 26 lks. dist., marked T.2 S., R.33 E., S.36, B.T. ?
	A pine, 10 ins. diam., brs. S.35° E., 75 lks. dist., marked T.3 S., R.33 E., S.1, B.T. ?
	A fir, 36 ins. diam., brs. S.25° W., 11 lks. dist., marked T.3 S., R.33 E., S.2, B.T.
	A fir, 5 ins. diam., brs. N.40° W., 33 lks. dist., marked T.2 S., R.33 E., S.35, B.T. ?
	I obliterate the marks referring to T.2 S. and set, at point of intersection, a basalt stone, 14 x 10 x 8 ins., 10 ins. in ground, for Closing Cor. to Secs. 33 & 34 marked 3 notches on E. & W. faces, C.C. on N. face; raised mound of stone. 1½ ft. high x 3½ ft. base over Cor., from which,
	A fir, 5 ins. diam., brs. S.2° E., 105 lks. dist., marked T.3 S., R.33 E., B.T.
	A pine, 20 ins. diam., brs. N.20° W., 143 lks. dist. marked T.2 S., R.33 E., S.33, B.T.
	A fir, 30 ins. diam., brs. N.50° E., 214 lks. dist., marked T.2 S., R.33 E., S.34, B.T.
	Land; mountainous, 53.50 chs.
	Heavily timbered with pine, fir & tamarack, with dense undergrowth of same, 47.50 chs. Soil; 4th rate.
	Var. 2° 00' E.
	Sept. 17, 1891.
	I commence at Closing Cor. to Secs. 4 & 5 on Reservation Bdy. which is a willow post, 2 ins. sq., x 33 ins. above ground in mound of stone, 1 ft. high x 2½ ft. base, marked U.R. on N. and C.C. on S. sides.
	Thence I run Descend.
	South bet. Secs. 4 & 5.