

## Exterior &amp; Subdivisional Lines, T. 2 S., R.33 E., W.M.

| Chains |   |                | Feet. |
|--------|---|----------------|-------|
|        | S. bet. Secs. 20 & 21.  | Ascend 40°     |       |
|        |   | Var. 17°45' E. |       |
| 5.50   | Summit of ridge falls W.  | Descend,       |       |
| 15.50  | Enter brush.  |                |       |
| 30.50  | Ravine N.5°W.   | Ascend         | -75   |
| 40.00  | Set basalt stone, 12 x 8 x 6 ins., 9 ins. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on W. face; dug pits, 18 x 18 x 12 ins., N. & S. of Cor., 5 $\frac{1}{2}$ ft. dist. and made mound of earth, 2 ft. high x 3 $\frac{1}{2}$ ft. base over stone, from which, A pine, 30 ins. diam., brs. N.15°W., 96 lks. dist., marked $\frac{1}{4}$ S., B.T. on W. hillside. |                |       |
|        | No other tree in limits.  |                |       |
| 43.25  | Leave brush.  |                |       |
| 48.50  | Summit if ridge falls N.30° E.  | Descend.       |       |
| 69.25  | Canyon, S.75° E.  | Ascend         | -450  |
| 80.00  | Set basalt stone, 14 x 8 x 5 ins., 6 ins. in ground, for Cor. to Secs. 20, 21, 28 & 29, (Digging impracticable) marked 2 notches on S. and 4 notches on E. Cors. Raised mound of stone, 2 ft. high x 3 $\frac{1}{2}$ ft. base over stone on E. hillside. Pits impracticable.  |                |       |
|        | Land; mountainous & stony, 80.00 chs. Some grass.   |                |       |
|        | Scattering pine and fir trees, with dense growth of brush of same, 37.75 chs. Soil; 5th rate.   |                |       |
|        | E. on random line bet. Secs. 21 & 28.   |                |       |
|        |   | Var. 20°00' E. |       |
|        | Ascend 38° through scattering timber.   |                |       |
| 40.00  | Set temp. $\frac{1}{4}$ Sec. Cor.   |                |       |
| 80.23  | Intersect N. & S. line at Cor. to Secs. 21, 22, 27 & 28   |                |       |
|        | Thence I run  | Ascend.        |       |
|        | W. on true line bet. Secs. 21 & 28.   |                |       |
|        |   | Var. 19°45' E. |       |
| 5.23   | Summit of mountain brs. N.W.  | Descend.       |       |
| 30.73  | Ravine, course N.W.   | Ascend         | -100  |
| 37.23  | Summit of ridge falls N.W.  | Descend        | +400  |
| 40.12  | A basalt stone, in place, 18 x 12 x 10 ins., above ground,  |                |       |