

Exterior & Subdivisional Lines, T.2 S., R.33 E., W.M.

Chains			Feet
44.00	Summit of ridge falls N.W.	Descend 20°	+700
56.25	Canyon, N.80°W.	Ascend 25°	-150
65.00	Summit of ridge falls N.W.	Descend 15°	+100
80.00	Set basalt stone, 18 x 10 x 4 ins., 12 ins. in ground, for Cor. to Secs. 17, 18, 19 & 20, marked 3 notches on S. face & face & 5 notches on E. edge. Raised mound of stone, 2 ft. high x 4½ ft. base over Cor. Pits impracticable; from which, A pine, 15 ins. diam., brs. S.70°W., 163 lks. dist., marked T.2 S., R.33 E., S.19, B.T. No other tree in limits. W. hillside. Land; mountainous, 74.50 chs. Soil; 5th rate, & 4th rate. Timber; pine, fir & tamarack, with scattering undergrowth of same, 18.50 chs. Soil; bottom land, 5.50 chs., excellent. Sept. 23, 1891		
	E. on random line bet. Secs. 17 & 20	Var. 22°35'E.	
40.00	Set temp. ¼ Sec. Cor.		
80.16	Intersect N. & S. line, 40 lks. N. of Cor. to Secs. 16, 17, 20 & 21.		
	Thence I run	Descend 30°	
	N.89°43'W. on true line bet. Secs. 17 & 20.	Var. 17°45'E.	
2.16	Canyon, course N.	Ascend 35°	-400
18.16	Summit of ridge falls N.15°W.	Descend 35°	+450
34.46	Ravine N.28°W.	Ascend 35°	-450
40.08	Set basalt stone, 14 x 10 x 6 ins., 6 ins. in ground, for ½ Sec. Cor. (digging impracticable), marked ½ on N. face, raised mound of stone, 1½ ft. high x 3½ ft. base over Cor. Pits impracticable, on E. hillside.		
50.16	Summit of ridge, brs. N. & S.	Descend 20°	+700
80.16	The Cor. to Secs. 17, 18, 19 & 20. Land; mountainous, 80.16 chs. No timber. Soil; stony 5th rate.		