

Exterior Lines, T.2 S., R.33 E., W. M.

Chains	<p>A fir, 14 ins. diam., brs. S.52°E., 35 lks. dist., marked S.31, B.T.</p> <p>A pine, 16 ins. diam., brs. S.43°W., 62 lks. dist., marked R.33 E., S.36, B.T.</p> <p>A pine, 20 ins. diam., brs. N.85°W., 96 lks. dist., marked S.25, B.T.</p> <p>Land; rolling.</p> <p>Soil; 2nd rate.</p> <p>Timber; pine, fir & tamarack, with dense underbrush & fallen timber of the same, 49.50 chs.</p>	
N. bet. Secs. 25 & 30.		
Var. 23°30'E.		
4.00	Wagon road, course S.W.	
40.00	Set post, 36 x 3 x 3 ins., 2 ft. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ S. on W. face, from which,	
	A pine, 16 ins. diam., brs. S.56°E., 2 lks. dist., marked $\frac{1}{4}$ S., B.T.	
	A pine, 20 ins. diam., brs. N.70°W., 32 lks. dist., marked $\frac{1}{4}$ S., B.T.	
68.50	Caravan & wagon road, W.	-600
69.00	Head waters of Birch Creek, water in holes. Leave timber. Ascend.	
80.00	Set basalt stone, 12 x 10 x 6 ins., 8 ins. in ground, for Cor. to Secs. 19, 24, 25 & 30, marked with 2 notches on S. and 4 on N. edges. Raised mound of stone around it. Pits impracticable.	+100
Land; rolling & mountainous.		
Timber; dense pine, fir & tamarack, with underbrush, 69 chs.		
Soil; 3rd rate. Mountainous, 11.00 chs.		
N. bet. Secs. 19 & 24.		
Var. 19°20'E.		
8.00	Top of ridge, course S.W.	+500
18.00	Canyon, " "	-300
30.00	Top of ridge, " "	+400