

Exterior Lines, T.2 S., R.33 E., W. M.

Chains

40.00 Set basalt stone, 9 x 8 x 7 ins., 6 ins. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on W. face. Raised mound of stone alongside. Pits impracticable.

47.75 Ravine, course E.

80.00 Set basalt stone, 20 x 10 x 4 ins., 15 ins. in ground, for Cor. to Secs. 1, 6, 7 & 12, marked with 5 notches on S. and one on N. edges. Raised mound of stone alongside. Pits impracticable.

Land; rolling and mountainous.

Soil; 4th rate.

Timber; pine, fir & tamarack in ravines.

Good bunch grass.

Mountainous, 50 chs.

N. bet. Secs. 1 & 6.

Var. 25°50'E.

7.00 Begin to descend.

40.00 Set basalt stone, 10 x 8 x 7 ins., 7 ins. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ in W. face, from which,

A pine, 8 ins. diam., brs. N.12°E., 112 lks. dist., marked $\frac{1}{4}$ S., B.T.

A pine, 24 ins. diam., brs. S.80°W., 99 lks. dist., marked $\frac{1}{4}$ S., B.T.

60.50 Gulch, course N.E. Water in holes.

80.00 Set basalt stone, 24 x 10 x 8 ins., 18 ins. in ground, for Cor. to Tps. 1 & 2 S., Rs. 33 & 34 E., marked with 6 notches on N., S., W. & E. edges. Raised mound of stone alongside. Pits impracticable.

A rock, 10 x 6 x 4 ft., above ground, brs. S.55°E., 125 lks. dist.

Land; mountainous, 80 chs.

Soil; 4th rate.

Scattering pine timber in canyons. Good bunch grass.

June 23, 1887.