

## Subdivisional Lines, T.2 S., R.33 E., W.M.

Chains		Feet
	<p><math>\frac{1}{2}</math> Sec. &amp; U.R. Closing Cor., marked <math>\frac{1}{2}</math> U.R.C.C. on N. face, over which, I raised mound of stone, 18 ins. high, with <math>3\frac{1}{2}</math> ft. base.</p> <p>Land; mountainous, 40 chs. Soil; 2nd rate.</p>	over
	<p>W. on true line bet. Secs. 10 &amp; 15.</p> <p style="text-align: right;">Var. 20°E.</p>	
5.40	Ridge and Wagon road, S.W.	
24.00	Head of canyon, N.	- 75
33.64	Intersect U.R. Bdy., 2.00 chs., S. 16°E., of $\frac{1}{2}$ mile Cor., on 74th mile.	
	<p>Set basalt stone, 10 x 12 x 16 ins., 10 ins. in ground, for U.R. Closing Cor., marked U.R. C.C. on E. face, over which, I raised mound of stone, 2 ft. high with <math>4\frac{1}{2}</math> ft. base.</p> <p>Land; broken. Soil; 2nd rate.</p>	- 50
	<p>FROM Cor. to Secs. 4, 5, 32 &amp; 33 on N. Bdy. of Tp., I run S. on true line bet. Secs. 4 &amp; 5.</p> <p style="text-align: right;">Var. 21°E.</p>	
10.00	Gulch, E.	-100
22.50	" "	-100
39.50	" "	-100
40.00	Set basalt stone, 12 x 10 x 8 ins., 8 ins. in ground, for $\frac{1}{2}$ Sec. Cor., marked $\frac{1}{2}$ on W. face; raised mound of stone, 18 ins. high with $3\frac{1}{2}$ ft. base alongside.	
52.00	Top of ridge, E.	+200
64.25	Gulch, E.	-200
69.80	Intersect U.R. Bdy, 7.80 chs., N. 30°W. of $\frac{1}{2}$ mile Cor. in 76th mile.	
	<p>Set post, 4 ft. long x 4 ins. sq., 24 ins. in ground, for U.R. Closing Cor., marked U.R. C.C. on N. face, around which, I raised mound of stone, 2 ft. high with <math>4\frac{1}{2}</math> ft. base.</p>	
75.00	Day Wagon road on ridge, N.W.	
80.00	Set stone, 7 x 8 x 20 ins., 14 ins. in ground, for Cor. to	