

Exteriors, T.2 S., R.35 E., W.M.

Chains		Feet
	N. bet. Secs. 25 & 30.	
		Var. 18° 50' E.
	Descend through dense timber.	
15.00	Leave dense timber.	
17.25	A pine, 2 ft. in diam.	
21.00	Enter timber.	
29.75	Bottom of ravine, course N.E. Ascend through open timber.	
36.25	Summit of point.	
37.00	Enter dense forests of young timber and much fallen timber.	
40.00	Set post, 3 ft. long, 3 ins. sq., 18 ins. in ground, on table land, covered with dense forest of timber, 3000 ft. above stream, on the N.E. face $\frac{1}{4}$ Secs. Cor., marked $\frac{1}{4}$ S. on E. & W. faces, from which, A fir, 5 ins. diam., brs. W., 31 lks. dist., marked $\frac{1}{4}$ S., B.T. A tamarack, 10 ins. diam., brs., N. 87° W., 30 lks. dist., marked $\frac{1}{4}$ S., B.T.	
		Var. 20° E.
	Descend through dense timber.	
51.50	Leave timber.	
52.15	Point of rocks.	
52.50	Ravine, course N.E.	
54.00	Point of basaltic rock, descend along eastern base of bluff.	
58.40	A fir, 38 ins. diam., Descend over loose rocks, abruptly.	
80.00	Set post, 4 ft. long, 4 ins. sq., 2 ft. in ground, among loose rock, 20 ft. above stream, course N.W., in deep rugged canyon, for Cor. to Secs. 19, 24, 25 & 30, marked, T.2 S., S.19 on N.E. R.35 E., S.30 on S.E. R.34 E., S.25 on S.W. and S.24 on N.W. faces, with 2 notches on S. and 4 notches on N. edges, from which, A fir, 40 ins., diam., brs. S. 79° E., 44 lks. dist., marked T.2 S., R.35 E., S.30, B.T.	