

## Exteriors, T. 2 S., R. 35 E., W.M.

Chains		Feet
	N. bet. Secs. 13 & 18.	
2.50	Brink of canyon, 1000 ft. deep, course W., measure with micrometer to	Var. 24° 45' E.
13.52	N. brink of canyon, course W. Over table land covered with heavy timber.	
40.00	Set post, 3½ ft. long, 3 ins. sq., 18 ins. in ground, in open pine timber, for ¼ Sec. Cor., marked ¼ S. on E. & W. faces, from which, A fir, 5 ins. diam., brs. N. 37° W., 18 lks. dist., marked ¼ S., B.T. A pine, 46 ins. diam., brs. N. 43° E., 70 lks. dist., marked ¼ S., B.T.	
		Var. 20° 15' E.
	Descend through heavy timber.	
45.50	Enter dense fir thicket.	
55.00	Leave thicket.	
77.50	Brink of canyon.	Descend.
80.00	Set post, 4 ft. long, 4 ins. sq., 2 ft. in ground, on steep N. hillside, 400 ft. above bottom of canyon, in dense fir timber, for Cor. to Secs. 7, 12, 13 & 18, marked T. 2 S., S. 7 on N.E. R. 35 E., S. 18 on S.E. T. 2 S., S. 13 on S.W. and S. 12 on N.W. faces, with 4 notches on S. and 2 notches on N. edges, from which, A fir, 16 ins. diam., brs. N. 52° E., 44 lks. dist., marked T. 2 S., R. 35 E., S. 7, B.T. A fir, 16 ins. diam., brs. N. 14° W., 73 lks. dist., marked T. 2 S., R. 34 E., S. 12, B.T. A fir, 10 ins. diam., brs. S. 31° E., 32 lks. dist., marked T. 2 S., R. 35 E., S. 18, B.T. A fir, 10 ins. diam., brs. S. 3° W., 12 lks. dist., marked T. 2 S., R. 34 E., S. 12, B.T.	
	Land; rough, mountainous & broken. Soil; rocky 4th rate. Timber; pine, fir & tamarack.	