

## Exteriors, T. 2 S., R. 35 E., W.M.

Chains		Feet
	N. bet. Secs. 1 & 6.	
		Var. 24° 10' E.
	Descend through open timber.	
15.00	Head of hollow, dense timber and undergrowth.	
35.00	Leave dense timber and enter open pine timber.	
40.00	Set post, 3 ft. long, 3 ins. sq., 10 ins. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ S. on E. & W. faces, set on W. side of ravine, sloping W., from which, A pine, 34 ins. diam., brs. S. 17° W., 42 lks. dist., marked $\frac{1}{4}$ S., B.T.	
	Leave timber.	
50.00	Enter heavy pine timber.	
65.00	Brink of canyon.	Descend.
75.50	Bottom of canyon, course N.W.	Ascend.
76.50	Leave timber.	
80.00	Set post, 4 $\frac{1}{2}$ ft. long, 4 ins. sq., 2 ft. in ground, on steep hillside, facing E. and 300 ft. above bottom of canyon and 400 ft. below summit, for Cor. to Tps. 1 & 2 S., R. 34 and 35 E., marked T. 1 S., S. 31 on N.E. R. 35 E., S. 6 on S.E. T. 2 S., S. 1 on S.W. R. 34 E., S. 36 on N.W. faces, with 6 notches on E. edge, from which, A pine, 8 ins. diam., brs. N. 26° E., 112 lks. dist., marked T. 1 S., R. 35 E., S. 31, B.T.	
	No other tree in limits, raised mound of stone alongside.	Var. 17° 50' E.
	Land; rough, mountainous & broken.	
	Soil; rocky 4th rate.	
	Timber; pine, fir and tamarack.	
General Description		
This line runs across the head canyons of McKay Creek and they are almost impassable for man or beast.		
The table land in this Tp. is near the summit of the Blue		