

Subdivisional Lines, T.2 S.,R.34 E.,W.M.

Chains		Feet
	<p>A pine, 24 ins. diam., brs. S.76°E., 30 lks. dist., marked T.2 S.,R.34 E.,S.34,B.T.</p> <p>A pine, 42 ins. diam., brs. S.60°W.,2.00 chs. dist., marked T.2 S.,R.34 E.,S.33,B.T.</p> <p>No other trees within limits. Raised mound of stone alongside.</p> <p>Land; rolling.</p> <p>Pine & fir timber.</p> <p>Dense underbrush, 70 chs.</p> <p>Soil; 2nd rate.</p>	
	<p>S. on true line bet. Secs. 33 & 34.</p> <p>Var. 18°30'E.</p>	
36.00	Leave timber, E. & W.	
40.00	Set basalt stone, 4 x 10 x 14 ins., 10 ins. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on W. face, over which, I raised mound of stone, 1 $\frac{1}{2}$ ft. high with 3 $\frac{1}{2}$ ft. base, as per instructions.	
50.25	Intersect U.R. Bdy., 5.42 chs., W. of $\frac{1}{2}$ mile Cor. in 65th mile and	
	Set basalt stone, 4 x 8 x 12 ins., 8 ins. in ground, for U.R. Closing Cor., marked U.R., C.C. on N. face, and raised mound of stone, 2 ft. high with 4 ft. base over it, as per instructions.	
	Land; rolling.	
	Good pine & fir timber.	
	Soil; 4th rate and rocky.	
	<p>N. on true line bet. Secs. 27 & 28.</p> <p>Var. 18°30'E.</p>	
32.00	Leave timber and brush.	
35.75	Gulch W. and ascend.	
40.00	Set basalt stone, 7 x 8 x 12 ins., 8 ins. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on W. face, over which, I raised mound of stone, 18 ins. high with 3 $\frac{1}{2}$ ft. base.	
42.25	Enter brush, E. & W.	
62.50	Ravine and leave brush	