

Subdivisional Lines, T. 2 S., R. 34 E., W.M.

Chains		Feet
74.50	Daly Wagon Road	
80.00	<p>Set post, 4 ft. long, 4 ins. sq., 24 ins. in ground, for Cor. to Secs. 21, 22, 27 & 28, marked</p> <p style="padding-left: 40px;">T.2 S., S.22 on N.E.</p> <p style="padding-left: 40px;">R.34 E., S.27 on S.E.</p> <p style="padding-left: 40px;">S.28 on S.W. and</p> <p style="padding-left: 40px;">S.21 on N.W. faces, with</p> <p style="padding-left: 40px;">3 notches on E. and</p> <p style="padding-left: 40px;">2 notches on S. edges, from which,</p> <p style="padding-left: 40px;">A pine, 10 ins. diam., brs. N.50°E., 81 lks. dist., marked T.2 S., R.34 E., S.22, B.T.</p> <p style="padding-left: 40px;">A pine, 6 ins. diam., brs. S.58°E., 187 lks. dist., marked T.2 S., R.34 E., S.27, B.T.</p> <p style="padding-left: 40px;">A pine, 12 ins. diam., brs. S.15°W., 135 lks. dist., marked T.2 S., R.34 E., S.28, B.T.</p> <p>No other trees within limits. Raised mound of stone, 2ft. high, with 4 ft. base alongside.</p> <p>Land; rolling.</p> <p>Some fir, pine and tamarack timber.</p> <p>Heavy underbrush, 70 chs.</p> <p>Soil; 2nd rate.</p>	
	<p>E. on random line bet. Secs. 22 & 27</p> <p style="text-align: right;">Var.21°E.</p>	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
80.00	<p>Intersect N. & S. line, 25 lks. N. of Cor. to Secs. 22, 23, 26, & 27.</p> <p>Thence</p> <p style="padding-left: 40px;">N.89°49' W. on true line bet. Secs. 22 & 27.</p> <p style="text-align: right;">Var.22° E.</p>	
12.50	Gulch, S.W.	
31.00	Enter timber, N. & S.	
39.00	Leave timber. " "	
40.00	<p>Set basalt stone, 12 x 12 x 12 ins., 8 ins. in ground, for $\frac{1}{2}$ Sec. Cor., marked $\frac{1}{2}$ S. on N. face, from which,</p>	