

Subdivisional Lines, T. 2 S., R. 34 E., W.M.

Chains		Feet
	<p>A pine, 16 ins. diam., brs. N.50°W., 86 lks. dist.,                      marked <math>\frac{1}{4}</math> S., B.T.</p> <p>No other trees within limits. Raised mound of stone, 18 ins.                      high with <math>3\frac{1}{2}</math> ft. base over Cor., as per instructions.</p>	
48.00	Gulch, S.W.	
65.00	Enter pine thicket.	
76.00	Leave thicket.	
80.00	The Cor. to Secs. 21, 22, 27 & 28.	
	<p>Land; mostly level</p> <p>Some pine &amp; fir timber.</p> <p>Heavy underbrush, 40 chs.</p> <p>Soil; 2nd rate.</p>	
	N. on true line bet. Secs. 21 & 22.	
		Var. 21°E.
3.00	Enter pine thicket.	
40.00	<p>Set post, 3 ft. long, 3 ins. sq., 24 ins. in ground, for  <math>\frac{1}{4}</math> Sec. Cor., marked <math>\frac{1}{4}</math> on W. face, from which,</p> <p>A pine, 12 ins. diam., brs. N.65°W., 5 lks. dist.,                      marked <math>\frac{1}{4}</math> S., B.T.</p> <p>A red fir, 10 ins. diam., brs. S.20°E., 16 lks. dist.,                      marked <math>\frac{1}{4}</math> S., B.T.</p>	
63.25	Ravine brs. N.W.	- 50
80.00	<p>Set post, 4 ft. long, 4 ins. sq., 24 ins. in ground, for                      Cor. to Secs. 15, 16, 21 &amp; 22, marked</p> <p style="padding-left: 40px;">T. 2 S., S. 15 on N.E.</p> <p style="padding-left: 40px;">R. 34 E., S. 22 on S.E.</p> <p style="padding-left: 40px;">S. 21 on S.W. and</p> <p style="padding-left: 40px;">S. 16 on N.W. faces, with</p> <p style="padding-left: 40px;">3 notches on S. &amp; E. edges from which,</p> <p>A pine, 10 ins. diam., brs. N.30°E., 37 lks. dist.,                      marked T. 2 S., R. 34 E., S. 15, B.T.</p> <p>A pine, 24 ins. diam., brs. S.45°E., 42 lks. dist.,                      marked T. 2 S., R. 34 E., S. 22, B.T.</p> <p>A pine, 4 ins. diam., brs. N.50°W., 30 lks. dist.,                      marked T. 2 S., R. 34 E., S. 21, B.T.</p>	