

## Subdivisional Lines, T. 2 S., R. 34 E., W.M.

Chains		Feet
64.00	Jennings Creek, S.	
80.00	<p>Set post, 4 ft. long, 4 ins. sq., 24 ins. in ground, for            Cor. to Secs. 28, 29, 32 &amp; 33, marked,</p> <p style="padding-left: 40px;">T.2 S., S.28 on N.E.            R.34 E., S.34 on S.E.            S.33 on S.W. and            S.29 on N.W. faces, with            4 notches on E. and            1 notch on S. edges, from which,</p> <p>A pine, 4 ins, diam., brs. N.3°E., 10 lks. dist.,            marked T.2 S., R.34 E., S.28, B.T.</p> <p>A pine, 5 ins. diam., brs. S.30°E., 45 lks. dist.,            marked T.2 S., R.34 E., S.33, B.T.</p> <p>A tamarack, 5 ins. diam., brs. S.85°W., 30 lks. dist.,            marked T.2 S., R.34 E., S.32, B.T.</p> <p>A tamarack, 6 ins. diam., brs. N.45°W., 11 lks. dist.,            marked T.2 S., R.34 E., S.29, B.T.</p>	
	Good timber; asfir and pine.	
	Land; mostly level.	
	Soil; 2nd rate.	
	S. on true line bet. Secs. 32 & 33.	
	Var. 18°45'E.	
26.00	South fork of Jennings Creek, 10 lks. wide, course S.E.	
40.00	<p>Set post, 3 ft. long, 3 ins. sq., 24 ins. in ground, for  <math>\frac{1}{2}</math> Sec. Cor., marked <math>\frac{1}{2}</math> S. on W. face, from which,</p> <p style="padding-left: 40px;">A pine, 5 ins. diam., brs. N.42°E., 9 lks. dist.,            marked <math>\frac{1}{2}</math> S., B.T.</p> <p style="padding-left: 40px;">A tamarack, 5 ins. diam., brs. S.38°W., 7 lks. dist.,            marked <math>\frac{1}{2}</math> S., B. T.</p>	
51.10	<p>Intersect U.R.Bdy., 5.58 chs. W. of <math>\frac{1}{2}</math> mile Cor. in 66th mile            Set post, 4 ft. long, 4 ins. sq., 24 ins. in ground, for            U.R. Closing Cor., marked</p> <p style="padding-left: 40px;">T.2 S., R.34 E., U.R., C.C. on N. face,            S. 33 on E. and            S.32 on W. faces, from which</p>	