

## Subdivisional Lines, T.2 S., R.34 E., W.M.

Chains	Feet
	<p>S.20 on S.W. and  S.17 on N.W. faces, with  3 notches on S. and  4 notches on E. edges, from which,  A pine, 24 ins. diam., brs. N.70°E., 66 lks. dist.,  marked T.2 S., R.34 E., S.16, B.T.  A pine, 20 ins. diam., brs. S.70° E., 63 lks. dist.,  marked T.2 S., R.34 E., S.21, B.T.  A pine, 36 ins. diam., brs. N.10°W., 112 lks. dist.,  marked T.2 S., R.34 E., S.17, B.T.</p> <p>No other trees within limits. Raised mound of stone along-  side, 18 ins. high with 4½ ft. base.</p> <p>Land; gently rolling or sloping towards South.  Scattering pine and fir timber.  Soil; 3rd rate.</p>
	<p>E. on random line bet. Secs. 16 &amp; 21.  Var. 18°30'E.</p>
40.00	Set temp. ¼ Sec. Cor.
80.20	Intersect N. & S. line, 30 lks. N. of Cor. to Secs. 15, 16, 21 & 22.
	Thence
	N. 89°47' W. on true line Var. 20°15'E.
40.10	A fir, 4 ins. diam., which, I marked for ¼ Sec. Cor., marked ¼ S. on N. face, from which, A fir, 12 ins. diam., brs. N.65°E., 33 lks. dist., marked ¼ S., B.T. A fir, 6 ins. diam., brs. S.50°E., 17 lks. dist. marked ¼ S., B.T.
80.20	To Cor. to Secs. 16, 17, 20 & 21. Land; mostly level. Timber; pine and fir. Soil; 1st rate.