

Subdivisional Lines, T.2 S., R.34 E., W.M.

Chai ns		Feet
	N. on true line bet. Secs. 8 & 9. Var. 20°E.	
30.00	Gulch, N.E. Ascend.	-100
40.00	Set basalt stone, 8 x 10 x 12 ins., 8 ins. in ground, for ¼ Sec. Cor., marked ¼ S. on W. face, over which, I raised mound of stone, 18 ins. high with 3½ ft. base.	
56.00	Summit of ridge & begin to descend	
67.50	Gulch, N.W.	-120
75.00	Top of ridge	+100
80.00	Set post, 4 ft. long, 4 ins. sq, 24 ins. in ground, for Cor. to Secs. 4, 5, 8 & 9, marked, T.2 S., S.4 on N.E. R.34 E., S.9 on S.E. S.8 on S.W. and S.5 on N.W. faces, with 5 notches on S. and 4 notches on E., from which, A fir, 16 ins. diam., brs. N.55°E., 15 lks. dist., marked T.2 S., R.34 E., S.4, B.T. A fir, 10 ins. diam., brs. S.55°E., 65 lks. dist., marked T.2 S., R.34 E., S.9, B.T. A fir, 10 ins. diam., brs. S.89°W., 5 lks. dist., marked T.2 S., R.34 E., S.8, B.T. A pine, 10 ins. diam., brs. N.68°W., 18 lks. dist., marked T.2 S., R.34 E., S.5, B.T.	
	Land; mountainous and brushy in last 40 chs.	
	Soil; 3rd rate. Bunch grass good.	
	E. on random line bet. Secs. 4 & 9. Var. 20°E.	
40.00	Set temp. ¼ Sec. Cor. to Secs. 3, 4, 9 & 10. Thence N. 89°55' W. on true line.	
	Var. 17°30'E.	
	Descend.	