

Subdivisional Lines, T.2 S., R.34 E., W. M.

Chains		Feet
15.00	Canyon and dry bed of creek Ascend.	-1000
35.00	Top of ridge, N.E.	
39.95	Set stone, 7 x 8 x 9 ins., 8 ins. in ground, for $\frac{1}{4}$ Sect. Cor. marked $\frac{1}{4}$ on N. face, over which, I raised mound of stone, 18 ins. high with $3\frac{1}{2}$ ft. base.	
45.00	Canyon, N.	-100
48.00	Top of ridge	+100
68.00	Canyon, N.W. Ascend.	-600
79.90	To Cor. to Secs. 4, 5, 8 & 9. Land; extremely mountainous, 79.90 chs. Some brush and scattering pine timber. Soil; 2nd rate. July 19, 1887.	
N. on true line bet. Secs. 4 & 5. Var. 20° E.		
15.00	Creek, 10 lks. wide, N.E. Ascend.	-1000
25.00	Bluff of rock.	+100
40.00	Set stone, 12 x 12 x 8 ins., 8 ins. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on W. face, over which, I raised mound of stone, 18 ins. high with $3\frac{1}{2}$ ft. base, on E. side of hill.	+900
55.00	Top of mountain . Descend.	+1000
70.00	Canyon, E.	-600
78.00	Intersect Tp. line, 3.95 chs. W. of Cor. to Secs. 32 & 33, T.1S., R.34 E. Set post, 4 ft. long, 4 ins. sq., 24 ins. in ground, for Closing Cor. to Secs. 4 & 5, marked T.2 S., R.34 E. on S. S.4 on E. and S.5 on W. faces, with 4 notches on E. and 2 notches on W. edges, from which,	