

## Subdivisional Lines, T.2 S., R.34 E., W. M.

Chains		Feet
25.35	Jennings Creek, N.E.	
40.00	Set post, 3 ft. long, 3 ins. sq., 24 ins. on ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ S. on W. face, from which, A pine, 20 ins. diam., brs. N.55°W., 46 lks. dist., marked $\frac{1}{4}$ S., B.T. A pine, 24 ins. diam., brs. S.67°E., 24 lks. dist., marked $\frac{1}{4}$ S., B.T.	
50.27	Intersect U.R. Bdy., 5.80 chs. W. of $\frac{1}{2}$ mile Cor. in 67th mile. Set post, 4 ft. long., 4 ins. sq., 24 ins. in ground, for Closing Cor. to Secs. 31 & 32, marked T.2 S., R.34 E. on N. S.32 on E. and S.31 on W. faces, from which, A pine, 36 ins. diam., brs. N.45° E., 121 lks. dist., marked T.2 S., R.34 E., S.32, C.C., B.T. A pine, 8 ins. diam., brs. N.57°W., 77 lks. dist., marked T.2 S., R.34 E., S.31, C.C., B.T. Land; rolling. Good timber; pine, tamarack and fir. Soil; 3rd rate and rocky.	
	W. on true line bet. Secs. 30 & 31. Var. 19°15'E.	
5.08	Wagon Road, N.E.	
40.00	Set post, 3 ft. long, 3 ins. sq., 24 ins. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ S. on N. face, from which, A pine, 8 ins. diam., brs. S., 13 lks. dist., marked $\frac{1}{4}$ S., B.T. A pine, 6 ins. diam., brs. N.43°W., 22 lks. dist., marked $\frac{1}{4}$ S., B.T.	
42.20	Wagon Road, N.W.	
45.00	Creek, 10 lks. wide, N.E.	
66.50	" " " " , S.E.	
75.00	Wagon Road, N.E. & S.W.	
79.20	Intersect W. Bdy., 2.94 chs., N. of Cor. to Secs. 25 & 32,	