

Subdivisional Lines, T. 2 S., R. 34 E., W. M.

Chains		Feet
	Land; rolling and broken. Pine & fir timber, first $\frac{1}{2}$ mile. Soil; rocky & 3rd rate.	
	N. on true line bet. Secs. 19 & 20 Var. $19^{\circ}30'E.$	
13.00	Gulch, E.	-100
40.00	Set stone, 6 x 10 x 12 ins., 8 ins. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on W. face, around which, I raised mound of stone, 18 ins. high with $3\frac{1}{2}$ ft. base.	
51.60	Wagon Road, E. & W.	
55.20	Gulch, E.	- 30
71.50	Road, E. & W.	
80.00	Set post, 4 ft. long, 4 ins. sq., 24 ins. in ground, for Cor. to Secs. 17, 18, 19 & 20, marked T.2 S., S.17 on N.E. R.34 E., S.20 on S.E. S.19 on S.W. and S.18 on N.W. faces, with 5 notches on E. and 3 on S. edges, from which, A pine, 10 ins. diam., brs. $N.45^{\circ}E.$, 107 lks. dist., marked T.2 S., R.34 E., S.17, B.T. A pine, 24 ins. diam., brs. $S.67^{\circ}E.$, 64 lks. dist., marked T.2 S., R.34 E., S.20, B.T. A pine, 20 ins. diam., brs. $S.40^{\circ}W.$, 64 lks; dist., marked T.2 S., R.34 E., S.19, B.T. A pine, 20 ins. diam., brs. $N.45^{\circ}W.$, 110 lks. dist., marked T.2 S., R.34 E., S.18, B.T.	
	Land; mostly open prairie. Scattering pine timber. Bunch grass. Soil; 4th rate, rocky.	
	E. on random line bet. Secs. 17 & 20. Var. $20^{\circ}E.$	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
79.25	Intersect N. & S. line, at Cor. to Secs. 16, 17, 20 & 21.	