

Subdivisional Lines, T.2 S., R.34 E., W. M.

Chains		Feet
	Thence W. on true line.	
	Var. 18°30' E.	
14.50	Head of canyon, N.E.	
29.50	" " "	
39.62	Set post, 3 ft. long, 3 ins. sq., 24 ins. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ S. on N. face, from which, A fir, 5 ins. diam., brs. N.15 lks. dist., marked $\frac{1}{4}$ S., B.T. A fir, 8 ins. diam., brs. S.40°W., 19 lks. dist., marked $\frac{1}{4}$ S., B.T.	
67.50	Enter timber, N.E.	
79.25	To Cor. to Secs. 17, 18, 19 & 20. Land; rolling. Soil; 3rd rate. Pine & fir timber in canyons.	
	July 20, 1887.	
	W. on true line bet. Secs. 18 & 19.	
	Var. 20°E.	
40.00	Set stone, 6 x 8 x 14 ins., 8 ins. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on N. face, around which, I erected mound of stones, 18 ins. high with 3 $\frac{1}{2}$ ft. base.	
51.60	Gulch, 2.00 chs. S. of spring, course S.	
65.10	Wagon Road, N.W.	
79.20	Intersect Tp. line and U.R. Bdy., 3.83 chs. N. of Cor. to Secs. 13 & 24, T.2 S., R.33 E. and Set stone, 12 x 14 x 16 ins., 10 ins. in ground, for Closing Cor. to Secs. 18 & 19, marked C.C., U.R. on W. face, with 3 notches on N. & S. edges, around which, I raised mound of stone, 2 ft. high with 4 $\frac{1}{2}$ ft. base. Land; rolling and mostly prairie. Some bunch grass. Soil; 3rd rate.	