

Subdivisional Lines, T. 2 S., R.34 E., W. M.

Chains		Feet
	N. on true line bet Secs. 17 & 18. Var. 20°E.	
15.00	Leave timber and enter prairie, E. & W.	
25.00	Enter timber.	
31.10	Canyon, N.E.	
40.00	Set post, 3 ft. long, 3 ins. sq., 24 ins. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ S. on W. face, from which, A pine, 8 ins. diam., brs. N.40°W., 10 lks. dist., marked $\frac{1}{4}$ S., B.T. A fir, 12 ins. diam., brs. S.75°E., 21 lks. dist., marked $\frac{1}{4}$ S., B.T.	
45.00	Canyon, N.E.	- 50
60.00	Summit of ridge, N.E.	
73.00	Begin to descend.	
80.00	Set stone, 18 x 18 x 18 ins., 12 ins. in ground, for Cor. to Secs. 7, 8, 17 & 18, marked with 5 notches on E. and 4 on S. edges, from which, A fir, 20 ins. diam., brs. S.45°W., 5 lks. dist., marked T.2 S., R.34 E., S.19, B.T. No other trees within limits. Raised mound of stone, 2 ft. high with $4\frac{1}{2}$ ft. base around Cor.	
	Land; broken.	
	Soil; 4th rate.	
	Pine & fir timber on first $\frac{1}{2}$ mile. Some bunch grass.	
	E. on random line bet. Secs. 8 & 17. Var. 20°E.	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
79.60	Intersect N. & S. line, at Cor. to Secs. 8, 9, 16 & 17. Thence	
	W. on true line Var. 20°E.	
7.00	Canyon, N.	-300
39.80	Set stone, 8 x 10 x 10 ins., 6 ins. in ground, for $\frac{1}{4}$ Sec. marked $\frac{1}{4}$ on N. face, over which, I raised mound of stone, 18 ins. high, with $3\frac{1}{2}$ ft. base.	