

Subdivisional Lines, T.2 S., R.34 E., W. M.

Chains		Feet
50.00	Summit, N.	+100
61.50	Canyon, N.	-300
79.00	Intersect Tp. line, 4.00 chs. N. of Cor. to Secs. 1 & 12, T.2 S., R.33 E., and Set stone, 7 x 8 x 9 ins., 6 ins. in ground for Closing Co Cor. to Secs. 6 & 7, marked C.C., U.R. on E. face with 5 notches on S. and 1 notch on N. edges, over which, Raised stone, 2 ft. high with 4½ ft. base. Land; mountainous, 39 chs. Timber in canyons, some good bunch grass. Soil; 4th rate, rocky.	
	NN. bet. Secs. 5 & 6. Var. 19°30' E.	
8.10	Trail on summit, N.E.	+ 80
15.00	Descend.	
28.00	Head of gulch, W.	- 20
40.00	Set basalt stone, 4 x 12 x 14 ins., 8 ins. in ground, for ½ Sec. Cor., marked ½ S. on W. face, over which, I raised mound of stone, 18 ins. high with 3½ ft. base.	-400
73.00	Rock point W.	+ 20
76.93	Intersect Tp. line, 3.55 chs. W. of Cor. to Secs. 31 & 32, T.1 S., R.34 E., and Set stone, basalt, 8 x 10 x 16 ins., 11 ins. in ground, for Closing Cor. to Secs. 5 & 6, marked C.C. on S. face with 5 notches on E. and 1 on W. edges, from which-400 A pine, 12 ins. diam., brs. S. 23° W., 25 lks. dist., marked T.2 S., R.34 E., C.C., S.6, B.T. No other trees within limits. Raised mound of stone, 2 ft. high with 4½ ft. base around Cor. Land; mountainous, 40 chs. Good bunch grass. No timber. Soil; 3rd rate.	
	July 21, 1887	