

Resurvey Portion E.Bdy., T.2 S., R.34 E., W. M.

Chains		Feet
	<p>Timber; pine, fir and tamarack.</p> <p>Undergrowth, lodgepole pine, balsam & willow.</p>	
	<p>N., resurveying the line bet. Secs. 7 & 12.</p>	
	<p>Descend 230 ft., through scattering timber to</p>	
10.40	Dry gulch, course N.W., thence over low point.	
17.09	Dry gulch, course S.80°W., ascend S. slope 260 ft. to	
35.00	Top of ascent, brs. E. & W.; thence over rolling land.	
40.00	Set an iron post, 3 ft. long, 1 in. diam., 26 ins. in ground, for $\frac{1}{4}$ Sec. Cor., with brass cap, marked,	
	$\begin{array}{r} \frac{1}{4} \\ S12 S7 \\ \hline 1917 \end{array}$	
	from which,	
	A pine, 36 ins. diam., brs. S.82°30'E., 69 lks. dist., marked $\frac{1}{4}$ S7, B.T.	
	A pine, 16 ins. diam., brs. N.18°15'W., 60 lks. dist., marked $\frac{1}{4}$ S12, B.T.	
	The old $\frac{1}{4}$ Sec. Cor., brs. N.33°E., 35 lks. dist., which I destroy.	
80.00	Set an iron post, 3 ft. long, 2 ins. diam., 24 ins in ground, for Cor. to Secs. 1, 6, 7, & 12, with brass cap marked,	
	$\begin{array}{r} T2S \\ R34E R35E \\ \hline S1 S6 \\ \hline S12 S7 \\ \hline 1917 \end{array}$	
	from which,	
	A fir, 20 ins. diam., brs. N.3°45'E., 240 lks. dist., marked T.2 S., R.34 E., S.6, B.T.	
	A pine, 36 ins. diam., brs. S.32°45'E., 163 lks. dist., marked T.2 S., R.35 E., S.7, B.T.	
	A pine, 18 ins. diam., brs. S.62°W., 20 lks. dist., marked T.2 S., R.34 E., S.12, B.T.	
	A pine, 30 ins. diam., brs. N.34°W., 69 lks. dist., marked T.2 S., R.34 E., S.1, B.T.	
	The old Cor. of Secs. 1, 6, 7 & 12 brs. North, 32 lks. dist., which I destroy.	
	Land; rolling, bench and mountainous.	