

## Resurvey Subdivisional Lines, T.2 S., R.34 E., W. M.

Chains		Feet
35.44	Dry gulch, course N.E., turning E. about 200 ft. N. of line ascend 15 ft. to	
37.00	Top of low spur, slopes N., descend 40 ft. to	
39.81	Apportioned distance Set iron post, 3 ft. long, 1 in. diam., 26 ins. in ground, for $\frac{1}{4}$ Sec. Cor., with brass cap, marked,	
	$\frac{1}{4}$ S23 S26 1917	
	from which, A tamarack, 10 ins. diam., brs. S.69°E., 4 lks. dist., marked $\frac{1}{4}$ S.26, B.T. A tamarack, 8 ins. diam., brs. N.33°W., 7 lks. dist., marked $\frac{1}{4}$ S., 23, B.T.	
68.27	Descend irregular and broken N.E. & E. slope, 600 ft. to Brook, 5 lks. wide, course N.; ascend.	
70.12	Top of low spur, slopes N.; descend.	
71.12	Spring branch, course N.W.; ascend 360 ft. to	
79.62	The Cor. of Secs. 23, 24, 25 & 26. Land; mountainous. Soil; light loam, shallow, on basalt bedrock, 3rd rate. Timber; pine, fir and tamarack. Undergrowth; pine, nine bark and willow.	
39.88	From the Cor. of Secs. 22, 23, 26 & 27 N., retracing bet. Secs. 22 & 23. Over rolling land, through scattering timber & undergrowth. Fall 8 lks. W. of $\frac{1}{4}$ Sec. Cor., which is basalt stone, 18 x 12 x 10 ins., set in mound of stone, marked $\frac{1}{4}$ on W. face; from which, A pine, 18 ins. diam., brs. S.25°30'E., 71 lks. dist., blazes healed over, not opened. A pine, 16 ins. diam., brs. S.17°W., 33 lks. dist., blazes healed over, not opened. At point, 2 lks. N. of true Cor. Set iron post, 3 ft. long, 1 in. diam., 26 ins. in ground,	