

Re-survey Subdivisional Lines, T.2 S., R.34 E., W.M.

Chains	Feet
32.25	Bottom of canyon, course N.75°E., water in places, 570 ft. below Sec. Cor. Leave undergrowth; ascend 275 ft. through scattering timber to
40.00	Set iron post, 3 ft. long, 1 in. diam., 26 ins. in ground, for $\frac{1}{4}$ Sec. Cor., with brass cap, marked <div style="text-align: center;"> $\frac{1}{4}$ S15 S14 1917 </div> from which A pine, 15 ins. diam., brs. S.36°15'W., 141 lks. dist., marked $\frac{1}{4}$ S.15, B.T. A pine, 36 ins. diam., brs. N.18°45'E., 334 lks. dist., marked $\frac{1}{4}$ S.14, B.T. Ascend 190 ft. to
45.80	Top of spur, slopes E.; descend along broken E. slope, 425 ft. to
80.00	Set iron post, 3 ft. long, 2 ins. diam., 24 ins. in ground, for Cor. of Secs. 10, 11, 14 & 15, with brass cap, marked <div style="text-align: center;"> T2S R34E S10 S11 S15 S14 1917 </div> from which, A pine, 24 ins. diam., brs. N.10°45'E., 88 lks. dist., marked T.2 S., R.34 E., S.11, B.T. A pine, 24 ins. diam., brs. S.38°15'E., 56 lks. dist., marked T.2 S., R.34 E., S.14, B.T. A pine, 12 ins. diam., brs. S.15°15'W., 67 lks. dist., marked T.2 S., R.34 E., S.15, B.T. A fir, 10 ins. diam., brs. N.65°30' W., 108 lks. dist., marked T.2 S., R.34 E., S.10, B.T. Land; mountainous. Soil; scant, on basalt bedrock, 3rd rate. Timber; fir & pine. Undergrowth; fir, pine, ninebark, serviceberry & willow.