

## Re-survey Subdivisional Lines, T.2 S., R.34 E., W. M.

Chains		Feet
	N. 89°45'W., on random line, bet. Secs. 10 & 15.	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
80.45	Intersect N. & S. line, 12 lks. S. of Cor. of Secs. 9, 10, 15 & 16.	
	Thence	
	S. 89°40'E., on true line bet. Secs. 10 & 15.	
	Over mountainous land, through heavy timber & medium undergrowth.	
.75	Dry gulch, course N. 30°E., ascend 125 ft. to	
7.50	Top of ridge; brs. N. & S.; descend 360 ft. to	
18.00	Dry gulch, course N.; ascend 200 ft. to	
30.35	Cross draw, 60 ft. deep, opening N.	
40.22 $\frac{1}{2}$	Top of spur, slopes N.	
	Set iron post, 3 ft. long, 1 in. diam., 26 ins. in ground, for $\frac{1}{4}$ Sec. Cor.; with brass cap marked,	
	$\frac{1}{4} \text{S}10$ $\text{S}15$ $1917$	
	from which,	
	A fir, 10 ins. diam., brs. N. 18°E., 57 lks. dist., marked $\frac{1}{4}$ S. 10, B.T.	
	A fir, 5 ins. diam., brs. S. 40°W., 24 lks. dist., marked $\frac{1}{4}$ S. 15, B.T.	
	Descend 550 ft. to	
59.40	Bottom of canyon, dry gulch, 5 lks. wide; course N., ascend 600 ft. to	600 ft
	600 ft. to	
72.60	Summit of "Rocky Ridge", brs. N. & S., descend 200 ft. on E. slope to	
80.45	The Cor. of Secs. 10, 11, 14 & 15.	
	Land; mountainous.	
	Soil; rocky with scant loam, 3rd rate.	
	Timber; pine & fir.	
	Undergrowth; fir, pine, willow & ninebark.	
	N. 0°15'E., on true line, bet. Secs. 10 & 11.	
	Over mountainous land, through scattering timber and dense undergrowth.	