

Re-survey Subdivisional Lines, T.2 S., R.34 E., W.M.

Chains		Feet
	marked $\frac{1}{4}$ S.11, B.T.	
40.70	Descend bluff, 50 ft. high, brs. E. & W.	
43.76	Creek bed, 10 lks. wide, dry, course W., 240 ft. below $\frac{1}{4}$ Sec. Cor.	
47.00	Leave timber & brush, brs. E. & W., ascend 810 ft. to	
80.00	Set iron post, 3 ft. long, 2 ins. diam., 8 ins. in ground, surrounded by mound of stone, 3 ft. base, $1\frac{1}{2}$ ft. high, for Cor. of Secs. 1, 2, 11 & 12, with brass cap, marked,	
	T2S R34E S2 S1 S11 S12 1917	
	and raise mound of stone, 3 ft. base, 2 ft. high, W. of Cor.	
	Land; mountainous & rolling.	
	Soil; shallow & rocky, 3rd rate.	
	Timber; pine, fir & tamarack.	
	Undergrowth; willow, fir, ninebark, serviceberry & arrowood.	
	S.89°43'W., on random line, bet. Secs. 2 & 11.	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
79.64	Intersect N. & S. line, 7 lks. N. of Cor. of Secs. 2, 3, 10 & 11.	
	Thence	
	N.89°40'E., on true line, bet Secs. 2 & 11.	
	Over mountainous land, through heavy timber & dense undergrowth. Descend 15 ft. to	
1.30	Dry gulch, course N.W.; ascend 325 ft. to top of ridge.	
3.00	Leave timber & undergrowth, brs. N.W. & S.E.	
18.30	Top of ridge, brs. N.W. & S.E. Enter small timber & undergrowth, brs. N.W. & S.E. Descend broken N.E. slope, 500 ft.	
39.82	Set iron post, 3 ft. long, 1 in. diam., 26 ins. in ground, for $\frac{1}{4}$ Sec. Cor., with brass cap, marked,	
	S2 S11 1917	
	from which,	
	A fir, 14 ins. diam., brs. S.50°30'E., 50 lks. dist.,	