

## Retracement Portion Subdivisional Lines, T.2 S., R.34 E., W. M.

Chains		Feet
	<p>At the point of intersection, Set iron post, 3 ft. long, 2 ins. diam., 12 ins. in ground and 12 ins. in mound of stone, for Closing Cor. of Secs. 34 &amp; 35, with brass cap, marked,</p> <p style="text-align: center;">T2S R34E UIR 334 335 C C 1917</p> <p>from which, A fir, 24 ins. diam., brs. S.9°E., 38 lks. dist., marked C.C., T.2 S., R.34 E., S.35, B.T. A fir, 12 ins. diam., brs. S.70°W., 72 lks. dist., marked C.C., T.2 S., R.34 E., S.34, B.T.</p> <p>From this Cor., the old Closing Cor. of Secs. 34 &amp; 35, within the original Umatilla Indian Reservation, brs. N.89°49'W., 50 lks. dist.</p> <p>Land; rolling bench. Soil; light shallow loam on basalt rock, 2nd rate. Timber; lodgepole pine, yellow pine, fir &amp; tamarack. Undergrowth; none</p>	34 & 35
2.56	<p>From the Cor. of Secs. 3, 4, 33 &amp; 34, on S. Bdy. of Tp., previously described, N., bet. Secs. 33 &amp; 34. Over mountainous land, through heavy timber. Descend N.E. slope, 50 ft. to Jennings Creek, 50 lks. wide, course S.E. the creek is prac- tically dry at the present time; ascend 350 ft. to</p>	
29.66	<p>Intersect S. Bdy. of original Umatill Indian Reservation, N.89°27'W., 4.04 chs. from the 64½ Mile Cor.</p> <p>At the point of intersection Set iron post, 3 ft. long, 2 ind. diam., 12 ins. in ground and 12 ins. in mound of stone, for Closing Cor. of Secs. 33 &amp; 34, with brass cap, marked,</p> <p style="text-align: center;">T2S R34E UIR 333 334 C C 1917</p>	