

## Retracement Portion Subdivisional Lines, T.2 S., R.34 E., W. M.

## Chains

Commence at the  $\frac{1}{4}$  Sec. Cor. of Secs. 35 & 36, which is an old post, marked & witnessed as described by the surveyor general. To further perpetuate this Cor., I mark  
 A fir, 10 ins. diam., brs. N.80°E., 2 lks. dist.,  
 marked  $\frac{1}{4}$  S.35, B.T.  
 and raise mound of stone, 3 ft. base, 1 ft. high, around post.

Thence

S., retracing bet. Secs. 35 & 36.

3.92 Fall 15 lks. E. of Closing Cor. of Secs. 35 & 36, on E. Bdy. of original Umatilla Indian Reservation, which is located by reference to the bearing trees as described by the surveyor general. I perpetuate this Cor., as follows:  
 at the exact Cor. point, which is on the E. edge of the Umatilla Indian Reservoir

Set an iron post, 3 ft. long, 2 ins. diam., 24 ins. in ground for Closing Cor. of Secs. 35 & 36, with brass cap, marked

T2S R34E  
 S35 |  
 \ / S36  
 C C  
 1917

from which

A pine, 22 ins. diam., brs. N.24°E., 101 lks. dist.,  
 marked C C S 36 B T.

A fir, 6 ins. diam., brs. S.47°30'W., 23 lks. dist.,  
 marked C C S 35 B T.

The true course and distance of this line to the Closing Cor. is S.2°10'W., 3.92 chs.

This Cor. is 1.20 chs., S.20°25'W. from the 62 $\frac{1}{2}$  Mile Cor., on the U.I.R. Bdy.

From the Closing Cor.  
 S., continuing my measurements.

39.90 Fall 15 lks. W. of Cor. to Secs. 1, 2, 35 & 36, previously described.

The true course and distance of this line from the Closing Cor. is S.0°14'E., 35.98 chs.