

## Subdivisional Lines, T.2 S., R.35 E., W. M.

Chains		Feet
	<p>face, from which,</p> <p>A pine, 6 ins. diam., brs. N.72°E., 14 lks. dist., marked <math>\frac{1}{4}</math> S., B.T.</p> <p>A pine, 7 ins. diam., brs. N.82°W., 17 lks. dist., marked <math>\frac{1}{4}</math> S., B.T.</p>	
80.00	<p>Set post, 4 ft. long, 4 ins. sq., 24 ins. in ground, for Cor. to Secs. 21, 22, 27 &amp; 28, marked</p> <p>T.2 S., R.35 E., S.22 on N.E.</p> <p>T.2 S., R.35 E., S.21 on N.W.</p> <p>S.28 on S.W. and</p> <p>S.27 on S.E. faces, with</p> <p>2 notches on S. and</p> <p>3 notches on E. edges, from which,</p> <p>A pine, 9 ins. diam., brs. N.35°E., 8 lks. dist., marked T.2 S., R.35 E., S.22, B.T.</p> <p>A pine, 6 ins. diam., brs. N.57°W., 9 lks. dist., marked T.2 S., R.35 E., S.21, B.T.</p> <p>A pine, 10 ins. diam., brs. S.13°W., 17 lks. dist., marked T.2 S., R.35 E., S.28, B.T.</p> <p>A pine, 5 ins. diam., brs. S.39°E., 19 lks. dist., marked T.2 S., R.35 E., S.27, B.T.</p> <p>Land; high &amp; mountainous table land.</p> <p>Soil; 2nd rate.</p> <p>Heavily timbered with pine, fir and tamarack and</p> <p>Dense undergrowth of pine, fir and tamarack.</p>	
	<p>N. bet. Secs. 21 &amp; 22.</p> <p style="text-align: right;">Var. 20°E.</p>	
6.00	<p>Indian Trail, brs. N.60°W &amp; S.60°E., and hole of water brs. E. about 150 lks. dist., in small meadow.</p>	
6.65	<p>Dry gulch, course N.60°W.</p>	
40.00	<p>Set post, 3 ft. long, 3 ins. sq., 24 ins. in ground, for <math>\frac{1}{4}</math> Sec. Cor., marked <math>\frac{1}{4}</math> S. on W. face, from which,</p> <p>A fir, 4 ins. diam., brs. S.67°E., 9 lks. dist., marked <math>\frac{1}{4}</math> S., B.T.</p>	