

Subdivisional Lines, T.2 S., R.35 E., W. M.

Chains		Feet
58.75	Same bed of creek, 5 lks. wide, course N.20°E., and ascend	
80.00	Set post, 4 ft. long, 4 ins. sq., 24 ins. in ground, for Cor. to Secs. 9, 10, 15 & 16, 300 ft. above bed of creek, marked,	
	T.2 S., R.35 E., S.10 on N.E.	
	T.2 S., R.35 E., S.9 on N.W.	
	S.16 on S.W. and	
	S.15 on S.E. faces, with	
	4 notches on S. and	
	3 notches on E. edges, from which,	
	A fir, 7 ins. diam., brs. N.38°E., 29 lks. dist.,	
	marked T.2 S., R.35 E., S.10, B.T.	
	A fir, 10 ins. diam., brs. N.31°W., 20 lks. dist.,	
	marked T.2 S., R.35 E., S.9, B.T.	
	A pine, 10 ins. diam., brs. S.47°W., 7 lks. dist.,	
	marked T.2 S., R.35 E., S.16, B.T.	
	A pine, 7 ins. diam., brs. S.13°E., 38 lks. dist.,	
	marked T.2 S., R.35 E., S.15, B.T.	
	Land; high & mountainous,	
	Soil; 3rd rate, stony.	
	Heavily timbered with pine, fir and tamarack and	
	Dense undergrowth of pine, fir and tamarack.	

	N. bet. Secs. 9 & 10.	
	Var. 17°30'E.	
	And descend.	
28.77	Dry ravine, course N.E., 300 ft. below Sec. Cor.	
40.00	Set post, 3 ft. long, 3 ins. sq., 24 ins. in ground, for Sec. Cor., marked $\frac{1}{4}$ S. on W. face, from which,	
	A fir, 12 ins. diam., brs. N.49°E., 33 lks. dist.,	
	marked $\frac{1}{4}$ S., B.T.	
	A fir, 12 ins. diam., brs. N.67°W., 16 lks. dist.,	
	marked $\frac{1}{4}$ S., B.T.	
70.00	Dry bed of creek in canyon, 8 lks. wide, course N.W., 200 ft. below $\frac{1}{4}$ Sec. Cor., and ascend.	