

## Subdivisional Lines, T.2 S., R.35 E., W. M.

Chains		Feet
	<p>Discontinued line at this Cor., as N. Bdy. of Tp. was discontinued at the <math>\frac{1}{4}</math> Sec. Cor., bet. Secs. 4 &amp; 33, on acct. of rugged country and Indian Reservation.</p> <p>Land; high &amp; mountainous.</p> <p>Soil; 2nd rate.</p> <p>Heavily timbered with pine, fir and tamarack, and Dense undergrowth of Pine, fir, tamarack and mountain laurel.</p>	
	<p>From Cor. to Secs. 5, 6, 31 &amp; 32, on S. Bdy. of Tp., which I run</p> <p>N. bet. Secs. 31 &amp; 32. Var. 23°40'E.</p> <p>*****</p>	
80.000	<p>Set post, 4 ft. long, 4 ins. sq., 24 ins. in ground, for Cor. to Secs. 29, 30, 31 &amp; 32, marked,</p> <p>T.2 S., R.35 E., S.29 on N.E.</p> <p>T.2 S., R.35 E., S.30 on N.W</p> <p>S.31 on S.W. and</p> <p>S.32 on S.E. faces, with</p> <p>1 notch on S. and</p> <p>5 notches on E. edges, from which,</p> <p>A tamarack, 10 ins. diam., brs. N.15°E., 10 lks. dist., marked T.2 S., R.35 E., S.29, B.T.</p> <p>A tamarack, 24 ins. diam., brs. N.27°W., 66 lks. dist., marked T.2 S., R.35 E., S.30, B.T.</p> <p>A fir, 15 ins. diam., brs. S.22°W., 73 lks. dist., marked T.2 S., R.35 E., S.31, B.T.</p> <p>A fir, 40 ins. diam., brs. S.37°E., 43 lks. dist., marked T.2 S., R.35 E., S.32, B.T.</p> <p>Land; high &amp; mountainous.</p> <p>Soil; 2nd rate.</p> <p>Heavily timbered with pine, fir &amp; tamarack, 69 chs. and Dense undergrowth of pine, fir and tamarack.</p>	
	<p>E. on random line bet. Secs. 29 &amp; 32.</p> <p>Var. 23°30'E.</p>	