

Subdivisional Lines, Pt 2 Sec. 36 E. W. M.

Chains		Feet
	E. on random line bet. Secs. 8 & 17. Var. 20°E.	
21.45	Old Indian Trail, brs. N.20°W. & S.20°E.	
32.00	Enter opening & enter timber, brs. N. & S.	
36.00	Leave opening & enter timber, brs. N. & S.	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor., 100 ft. above last Sec. Cor.	
50.00	Descend hill, brs. N. & S.	
67.00	Ravine, course N.E.	
74.25	Dry bed of McKay creek, 10 lks. wide, course N. 700 ft. below point of descending hill, and ascend.	
79.75	Intersect N. & S. line, 34 lks. S. of Cor. to Secs. 8, 9, 16 & 17, 150 ft. above bed of McKay creek. Thence I run S.89°45'W. on true line bet. Secs. 8 & 17.	
39.87	Set post, 3 ft. long, 3 ins. sq., 24 ins. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ S. on W. face, from which, A fir, 4 ins. diam., brs. N., 40 lks. dist., marked $\frac{1}{4}$ S., B.T. A tamarack, 10 ins. diam., brs. S.12°W., 37 lks. dist., marked $\frac{1}{4}$ S., B.T.	
79.75	The Cor. to Secs. 7, 8, 17 & 18. Land; high & mountainous. Soil; 2nd & 3rd rate. Heavily timbered with pine, fir, tamarack & spruce and Dense undergrowth of pine, fir, tamarack & spruce, 75.75 chs.	
	W. on true line bet. Secs. 7 & 18. Var. 20°E.	
	Gradual descent.	
40.00	Set post, 3 ft. long, 3 ins. sq., 24 ins. in ground, for $\frac{1}{4}$ Sec. Cor., 200 ft. below Sec. Cor., marked $\frac{1}{4}$ S. on W. face, from which, A pine, 12 ins. diam., brs. N.57°W., 8 lks. dist., marked $\frac{1}{4}$ S., B.T. A pine, 14 ins. diam., brs. S.21°W., 30 lks. dist., marked $\frac{1}{4}$ S., B.T.	